Bruhat Bangalore Mahanagar Palike

Dasarahalli Zone

Executive Engineer Electrical
Dasarahalli Zone
Bruhat Bangalore Mahanagar Palike

Negotiated Schedule-B

	BBMP/2019-20/EL/WORK_INDENT37495/CALL-2						
	Improvements of damaged electrical poles shifting to electrical poles and other electrical works in						
SNo	Item Name	Item Code	Unit	Estimate Quantity	2019-20 CSR Rate	MANJUNATHA S G S ELECTRICALS Tender Quoted Rate	MANJUNATHA S G S ELECTRICALS Negotiated rate
1	Supplying heavy gauge PVC Conduit Pipe ....dia .....mm thick with suitable size bends, metal junction boxes adhesive paste etc., by groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the wall surface and run with 18 SWG GI fish wire run throughout the conduit wherever necessary.25mm dia 2mm thick	1	Mtrs	100	65.00	60.0	60.0
2	Supplying and fixing surface/flush mounting unbreakable PVC modular box suitable for mounting modular switch plates with due groove cutting in Brick/C.C wall, including necessary rawl plugs, Machine/NF screws etc., complete.10-12Way	2	Nos	10	160.00	60.0	60.0
3	Supply and fixing of Bakelite D.P/Socket/ switch with/without neon indicator over existing wood board or flush mounting in plastic plates/nitches as per IS 1293 and IS 3854 GROUP A 32Amps Flush/projected type DP switch	3	Nos	10	187.00	60.0	60.0
4	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 GROUP A 16Amps one way switch	4	Nos	30	110.00	100.0	100
5	6/16Amps universal socket	5	Each	30	162.00	50.0	50
6	Stepped Fan Regulator.	6	Each	30	290.00	250.0	250

7	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A.1.5 sqmm	7	Mtrs	800	20.50	20.0	20.0
8	2.5 sqmm	8	Mtr.	400	32.00	25.0	25.0
9	Point wiring using Copper wire with switch. Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2 X1.5Sq.mm Cable confirming to the GTP, with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet / gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. GROUP B Short point upto 3Mtr from tapping point to out let via switch	9	Each	10	200.00	200.0	200
10	Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch	10	Each	10	275.00	150.0	150
11	Long point above 6Mtr upto 10Mtr from tapping point to out let via switch	11	Each	10	400.00	100.0	100
12	Supplay and Laying of 1.1KV Class HR (Heat Resistant) PVC Insulated & UnSheathed Aluminium Wires Multistrand Single core Lead wires as per IS694: 2010 PVC Wire - 25 Sqmm Al Wt: 6.7 Kgs, Total Wt: 11.5Kgs for 100Mtrs	12	Mtrs	100	32.31	50.0	50.
13	Supplay and Laying of 1.1KV Class HR (Heat Resistant) PVC Insulated & UnSheathed Aluminium Wires Multistrand Single core Lead wires as per IS694: 2010 PVC Wire 16 Sqmm Al Wt: 4.2 Kgs, Total Wt: 7.5Kgs for 100Mtrs	13	Mtrs	400	23.41	20.0	20.

	with pressure die cast aluminum housing body with optimal heat sink for better thermal dissipation. Diffuser with Injection moulded & is made of polycarbonate material with high transmission index, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminare > IK08. Power Factor >0.9 with mains Current should not be greater than 0.1A to 0.7A & Surge Protection- Min 4KV along with Over voltage/Overload, short circuit/ miswiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Over load & Short circuit protection ensures reliable operation in spite of problem in output side. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of						
14	maintenance at the sight site location	14	Nos	66	1840.00	6000.0	1800

Accepted

For G S ELECTRICALS

S. Thyagaraju

Proprietor

Executive Engineer (Ele)
Bruhath Bangalore Mahanagara Palike
Dasarahalli Zone

15	System Power consumption pressure die cast aluminum housing with powder coating with IP 65 protection. 1, 200-275V voltage with electronic Driver, PF>0.9, should meet ANSI 2G Vibration test, Compliance to UL/CE with Class I. System rating shall be 50K hrs. @ Lumen maintenance of 70%, system efficacy > 80lm/w. Over load & Short circuit protection ensures reliable operation in spite of problem in output side. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with .....W System Power consumption. LED Efficiency>130lm/w at 1W & Fixture Efficiency >80lm/w with nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008. Housing with supplier word mark /name shall be Engraved /	15	Nos	6	7500.00	11500.0	7495
16	Fixing halogen/metal halide / SVL / IL / LED floodlight fitting over existing pole / wall ceiling including clamps, bolts, nuts and wiring using suitable capacity wires.	16	Nos	72	175.00	150.0	150
17	Supplying and fixing telescopic M.S. bracket fabricated by using 0.5m length 4" dia telescopic M. S. pipe, with 2" dia 1.5m long M. S. bracket and are welded with suitable angle, using 6mm thick M. S. sheet, grip bolts & nuts, as required, suitable for 9 to 12 mtrs. M. S. tubular pole, with necessary two coats of painting, with all other accessories.Single bracket 1.5 Mtr. Length	17	Nos	66	1200.00	1200.0	1200

18	Supplying box type suitable for 28W T5 single / twin Lamp & suspension mounted luminaire & optical reflector. Prewired with HF electronic Ballast, push fit type lamp holders & main connectors. Channel cover shall be made of CRCA MS Sheet and finishing is done with stove enameled white with end caps made of engineering plastic.1x4'-28 Watts	18	Nos	25	300.00	1500.0	1500
19	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system. 48" Sweep (1200mm)Regular model	19	Nos	15	2090.00	2500.0	2500
20	Fixing all types and all capacities of fluorescent / false ceiling / spot light / CFL / LED fittings indoor on the wall / ceiling / rafters / girders using 23/0.0076" twin twisted PVC insulated wires, required Nos of round blocks and clamps.On wall / ceiling / Rafter / Girders	20	Nos	25	110.00	200.0	200
21	Fixing a ceiling / Wall mounting fan of all capacities and all types to the existing 'S' hook with fan regulator to the existing board together with supplying and fixing 5 amps. ceiling rose, necessary length of 23 / 0.0076 inch PVC insulated twin twisted copper wire and wiring.	21	Nos	15	150.00	200.0	200
22	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A.4 core 16 sqmm	22	Mtrs	200	150.00	90.0	90
23	Labour charges for lying of 1.1 KV class UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall /on pole as required. I. In existing trench/duct.a)6 sqmm to 16 sqmm	23	Mtrs	200	15.50	20.0	20

24	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7)In soil (ordinary)	24	Per Mtr	170	76.00	50.0	50
25	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.II - Double Door 8Way SP &N	25	Nos	1	1450.00	5000.0	5000
26	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 5-32Amps SP	26	Nos	6	434.00	1200.0	1200
27	40-63Amps DP	27	Nos	1	1336.00	300.0	300
28	Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947.100-125Amps	28	Nos	1	7200.00	4500.0	4500
29	Supplying and fixing electro mechanical timer (without contactor) using necessary bolts, nuts and waqshers etc.. Group A, PWD Elec SR 2006-07.	29	Nos	1	4200.00	2500.0	2500
30	Supply and erection of .....Mtr RCC Pole including earth work etc,. complete as per the standard technical specification of BESCOM 9Mtr 145Kg WL	30	Nos	9	8029.00	15000.0	15000
31	Supplying of 1.1KV grade Aerial Bunched Cable Stranded & Compacted Aluminum Phase Conductor, and Stranded Messenger Conductor with all aluminum Alloy, Phase Conductor is insulated with XLPE Compound, insulated Messenger with specified IS-14255:1995 & confirming to GTP of GROUP-A.2 X 25 + 1 X 25 SQ.MM	31	Mtrs	300	143.00	150.0	150

2	Stringing of 1.1kv LT Arial Bunched Cable, BESCOM SR	32	Mtrs	300	10.30	25.0	25
33	Supply and fixing of .....cross arm including all Hardware's complete as per the standard technical specification of BESCOM 2 Pin 45x45x5mm -510mm	33	Nos	10	306.00	250.0	250
34	Suspension clamp suitable for insulated Messsenger wire of size 25 to 95Sq mm	34	Nos	10	325.00	150.0	150
35	Universal Hook and Bolts & Nuts	35	Nos	10	305.00	50.0	50
36	Dead End Clamp/Anchor Clamp Assembly 16 to 70 Sqmm Bare Messenger(Exclusive of pole clamp and eye hook)	36	Nos	4	200.00	150.0	150
37	Erection of Suspension Clamp - 25 to 95 sqmm bare messenger	37	Nos	10	115.00	125.0	125
38	Fixing of Universal Hook/Dead end clamp	38	Nos	4	115.00	50.0	50

Accepted

For G.S ELECTRICALS

Proprietor

Executive Engineer
Bruhath Bangalore Mahanagara Palike
Dasarahalli Zone